

VELA 900 direct

suspended

073-12716370




| |
|----------------|
| Project / Type |
| Notes |
| Count / Date |




Round luminaire housing in aluminium, rolled profile, seamlessly welded; surface white powder coated; highly reflective coating for improved efficiency; suspended luminaire with 1500mm cable suspension; with integrated tool-less suspension height adjustment; incl. feed (white); completely homogeneously illuminated, satinised PMMA cover; light colour 4000 K; binning initial MacAdam ≤ 3 SDCM; CRI ≥ 80 ; min. 90% of luminous flux after 50000 operating hours; energy efficient LEDs with high CRI; canopy with 2 cable openings and plug-in terminal for through wiring; degree of protection IP40; PC1 220-240V; photobiological safety according to IEC 62471 risk group RG 0 - no Risk; internal wiring in light halogen free; incl. DALI-2 converter; light source replaceable by an authorized professional; control gear replaceable by an authorized professional;

Light distribution



Product drawing



| | | | | | | |
|------|----------|--------|---------------|---------------|---------------|--------|
| IP40 | 220-240V | X-PERT | UGR ≤ 22 | CRI ≥ 80 | DALI-2 1ADDR. | X-PERT |
|------|----------|--------|---------------|---------------|---------------|--------|

General

| |
|------------------------------|
| Ceiling , Suspended |
| white , RAL9010 ¹ |
| IP40 |
| 9520 lm |

LED

| |
|---------------------------------|
| 4000 K |
| CRI ≥ 80 |
| L90 / 50000 h |
| photobio. safety RG 0 - no Risk |
| initial MacAdam ≤ 3 SDCM |
| MR 0.72 |
| MDER 0.66 |

Optical

| |
|-------------------------------|
| Opal |
| opal (lambertsch) |
| PstLM ≤ 1.0 ² |
| SVM ≤ 0.4 ² |

Electrical

| |
|--------------|
| DALI-2 |
| 71 W |
| PC1 220-240V |
| 134 lm/W |
| 1 DALI Addr. |

Physical

| |
|-----------------|
| cable 1500 mm |
| diameter 900 mm |
| height 87 mm |
| 12.3 kg |

¹ RAL code ² Value of containing product at full load (undimmed)

Installation instructions



Lighting calculator



VELA 900 direct

suspended

073-12716370



Project / Type

Notes

Count / Date

Maintenance Factors

| Operating Time [h] | 10 000 | 20 000 | 30 000 | 40 000 | 50 000 |
|--------------------|--------|--------|--------|--------|--------|
| LLMF | 0.98 | 0.95 | 0.93 | 0.91 | 0.9 |
| LSF | 1 | 1 | 1 | 1 | 1 |

MF

MF

LMF^a

LMF × RSMF × LLMF × LSF

Maintenance Factor

Luminaire Maintenance Factor

RSMF^a

LLMF

LSF

Room Surface Maintenance Factor

Lamp Lumens Maintenance Factor

Lamp Survival Faktor

^a According to "CIE 97, Maintenance of indoor electric lighting systems", 2005, ISBN 3-900-734-34-8. The values must be determined by the planner.

Circuit Breaker Types

| Automatic Circuit Breaker Type | Number of Fixtures |
|--------------------------------|--------------------|
| B10 | 9 |
| B13 | 12 |
| B16 | 15 |
| B20 | 19 |
| C10 | 15 |
| C13 | 20 |
| C16 | 25 |
| C20 | 31 |

