

VELA 600 direct / indirect power

suspended
073-125461GO



Project / Type _____

Notes _____

Count / Date _____



IP40

220-240V

X-PERT

UGR ≤ 22

CRI ≥ 80

X-PERT

General

Ceiling , Suspended

grey , RAL9006 ¹

IP40

indirect 1970 lm

direct 4350 lm

total 6320 lm

LED

4000 K

CRI ≥ 80

L90 / 50000 h

photobio. safety RG 0 - no Risk

initial MacAdam ≤ 3 SDCM

MR 0.72

MDER 0.66

Optical

Opal

opal (lambertsch)

PstLM ≤ 1.0 ²

SVM ≤ 0.4 ²

Electrical

non DIM

45 W

PC1 220-240V

140 lm/W

Physical

cable 1500 mm


diameter 600 mm

height 87 mm


5.8 kg

¹ RAL code ² Value of containing product at full load (undimmed)

Light distribution



Product drawing



Installation instructions



Lighting calculator



VELA 600 direct / indirect
power
suspended
073-125461GO



Project / Type _____

Notes _____

Count / Date _____

Maintenance Factors

Operating Time [h]	10 000	20 000	30 000	40 000	50 000
LLMF	0.98	0.96	0.94	0.91	0.9
LSF	1	1	1	1	1
MF	LMF × RSMF × LLMF × LSF		RSMF ^a	Room Surface Maintenance Factor	
MF	Maintenance Factor		LLMF	Lamp Lumens Maintenance Factor	
LMF ^a	Luminaire Maintenance Factor		LSF	Lamp Survival Faktor	

^a According to "CIE 97, Maintenance of indoor electric lighting systems", 2005, ISBN 3-900-734-34-8. The values must be determined by the planner.

Circuit Breaker Types

Automatic Circuit Breaker Type	Number of Fixtures
B10	7
B13	9
B16	11
B20	14
C10	12
C13	16
C16	19
C20	24

