

# TASK 450 round direct / indirect power

suspended

059-026103XP



Project / Type

Notes

Count / Date



### General

Ceiling , Suspended

special colours

IP40

indirect 1460 lm

direct 2710 lm

total 4170 lm

### LED

3000 K

CRI ≥ 90

L90 / 50000 h

initial MacAdam ≤ 3 SDCM

R<sub>g</sub>: 96 , R<sub>f</sub>: 90 , R<sub>(1-15)</sub>: 90

MR 0.61

MDER 0.56

### Optical

Microprismatic

microprismatic

UGR < 19

P<sub>stLM</sub> ≤ 1.0<sup>1</sup>

SVM ≤ 0.4<sup>1</sup>

### Electrical

DALI-2

220-240 V

system 38 W

system 110 lm/W<sup>2</sup>

PC1

1 DALI Addr.

### Physical


cable 1500 mm

diameter 450 mm


height 40 mm

3.6 kg

### Light distribution



### Product drawing



<sup>1</sup> Value of containing product at full load (undimmed)  
<sup>2</sup> FIXTURE: incl. consideration of optical losses & internal control unit losses SYSTEM: incl. consideration of optical losses, internal control unit losses & operating device efficiency.

### Installation instructions



### Lighting calculator



# TASK 450 round direct / indirect power

suspended

059-026103XP



Project / Type

Notes

Count / Date

## Circuit Breaker Types

Automatic Circuit Breaker Type	Number of Fixtures
B10	9
B13	13
B16	15
B20	18
C10	18
C13	26
C16	30
C20	36

