

# TASK 900 round direct / indirect power

suspended

059-046313XK



Project / Type

Notes

Count / Date



### General

Ceiling , Suspended

special colours

IP40

indirect 4370 lm

direct 9370 lm

total 13740 lm

### LED

4000 K

CRI ≥ 90

L90 / 50000 h

initial MacAdam ≤ 3 SDCM

R<sub>g</sub>: 96 , R<sub>f</sub>: 90 , R<sub>(1-15)</sub>: 87

MR 0.75

MDER 0.68

### Optical

Microprismatic

microprismatic

UGR < 19 , ≥65° <3000 cd/m<sup>2</sup>

P<sub>stLM</sub> ≤ 1.0<sup>1</sup>

SVM ≤ 0.4<sup>1</sup>

### Electrical

DALI-2

220-240 V

system 100 W

system 137 lm/W<sup>2</sup>

PC1

2 DALI Addr.

### Physical


rod 1000 mm

diameter 900 mm


height 41 mm

14.5 kg

### Light distribution



### Product drawing



<sup>1</sup> Value of containing product at full load (undimmed)  
<sup>2</sup> FIXTURE: incl. consideration of optical losses & internal control unit losses SYSTEM: incl. consideration of optical losses, internal control unit losses & operating device efficiency.

### Installation instructions



### Lighting calculator

